

**NEDES**

# QUOTE

**BASE BID**

QTY	UNIT	ITEM	DESCRIPTION	UNIT PRICE	LINE TOTAL
			<b>FLOORING</b>		
94	SF	Flooring	<b>Finish Tag: CT-1</b> Ceramic Tiles		\$ -
905	SF	Flooring	<b>Finish Tag: CT-2</b> Ceramic Tiles		\$ -
2181	SF	Flooring	<b>Finish Tag: LVT-1</b> Luxury Vinyl Tiles		\$ -
2181	SF	Flooring	Adhesive Under LVT		
9765	SF	Flooring	<b>Finish Tag: CPT-1</b> Carpet Tile		\$ -
9765	SF	Flooring	Patching Compound <b>(326 Bags)</b> <b>Material/Model:</b> Ardex K-15 <b>Thickness:</b> 1/4" Thk <b>Note: 1 Bag = 55 LBs</b> <b>(Note: Patching Compound Is Assumed Under Carpet Tiles)</b>		
9765	SF	Flooring	Adhesive Under Carpet Tile		
750	SF	Flooring	Quarry Tile		\$ -
228	SF	Flooring	Epoxy Paint Flooring		\$ -
			<b>WALL BASE</b>		
1386	LF	Wall Base	Wood Base		\$ -
292	LF	Wall Base	<b>Finish Tag: CT-2</b> Ceramic Tiles Base		\$ -
100	LF	Wall Base	Quarry Tile Base		\$ -
72	LF	Transition Strip	Floor Transition Strip <b>(12 EA)</b> <b>Note: 6' L Strip</b>		\$ -
58	LF	Transition Strip	Floor Transition Strip <b>(20 EA)</b> <b>Note: 3' L Strip</b>		\$ -
			<b>WALL TILES</b>		\$ -
114	SF	Wall Tile	Ceramic Wall Tiles @ Studio Bathrooms <b>(EA: 1028)</b> <b>Size: 4"x4"</b>		\$ -
512	SF	Wall Tile	Ceramic Wall Tiles@Mens And Women Toilets <b>(H: 6'-6")</b> <b>Note: There Is Not Wall Tile As Per Elevations, But In Finish Schedule It Is Mentioned To Have Wall Tile In Men And Women Restroom, So We Have Included Wall Tiles In Restrooms</b>		\$ -
			<b>GROUT</b>		\$ -
0.17	CY	Grout	Grout For Ceramic And Quarry Tile <b>(45 Bag, 2375 SF)</b> <b>NOTE: 1 Bag = 11 LBs</b>		\$ -
5	CY	Mortar	3/4" Thick Mortar For Ceramic And Quarry Tile		\$ -
				Sub-Total:	\$ -
				Tax:	15%
				Total:	\$ -
				Balance Due:	